





Republic of the Philippines  
Region 1  
DIVISION OF CITY SCHOOLS  
DAGUPAN CITY



Division Memorandum 246 2018

TO: All School Heads/Principals  
FROM:   
LORNA G. BUGAYONG  
Schools Division Superintendent  
DATE: April 12, 2018  
SUBJECT: DIVISION FIRE SAFETY COMPLIANCE REPORT

RELEASED  
DATE: 7/11/18  
BY: J. 9/15/18  
TRF 615

Relative to the Annual Fire Safety Inspection conducted by the Bureau of Fire Protection Dagupan City Station in our schools, attached is the Division Compliance Report for your reference.

Kindly furnish this Division a copy of your compliance report thru the DRRM and EFU Office on or before July 6, 2018.

For your compliance.



**DepED**  
DEPARTMENT OF EDUCATION  
Region I  
**SCHOOLS DIVISION OFFICE**  
Dagupan City



June 28, 2018

**CINSP GEORGIAN DM PASCUA**

City Fire Marshal  
Bureau of Fire Protection  
Dagupan City, Pangasinan

Sir:


Warm greetings from DepEd Dagupan City!

We would like to inform you that below are the actions taken on the deficiencies noted during the Fire Safety Inspection on our schools:

Defects / Deficiencies (Summary)	Remarks / Actions Taken
1. No Secondary Exit (ERB, FFCCI, BAYANIHAN, DPWH, etc.)	These bldgs were constructed from 1990s to early 2000 and during that time, the standard classroom sizes were 7m x 7m and 7m x 8m. As per NBCP, public facilities or structures with MORE THAN 50 occupants must be provided with 2 sets of egress, for 50 below 1 egress is allowed. As per consultation with DepEd Central Office, we were advised that starting 2019 Repair fund, addl. egress will be included in the POW for schools in the list.
2. Inadequate / failure to maintain / absence of portable fire extinguisher	Will be addressed by schools concerned.
3. Dangling Electrical Wirings / Poor Installation of Electrical Wirings / Open fuse box / uncovered junction box / busted convenience outlet / uncovered panel board / service wire at the tree	- Will be addressed by succeeding DepEd Funded Repairs; - SH to tap local electricians and be funded by School MOOE.
4. No directional exit signs	Will be addressed by schools concerned.
5. No wet standpipe system (For multi-storey bldgs)	As per DPWH, this reqmt will be reviewed first prior to recommendation to Central Office (DepEd and DPWH) for inclusion on the succeeding New Const. projects. For existing buildings, review and costing will be done by DepED CO prior to inclusion in succeeding repair funds.
6. Absence of fire alarm bell	Will be addressed by schools concerned.
7. Obstructed Hallways (DCNHS)	Will be addressed by schools concerned.
8. Insufficient size of stairs.	Width of stairs is as per Approved Plans and Specifications set by DepEd and DPWH.

For your information.

Very truly yours,



Dr. LORNA G. BUGAYONG, CESO VI  
Schools Division Superintendent

<b>RECEIVED</b>	
BY: <u>FD2 Elatos Vinwan</u>	
DATE: <u>July 02, 2018</u>	